


- ⊠ Survey corner
- ⊗ Rock source
- Ⓢ Stock pile
- Ⓜ Waste area
- ▨ Buffer zone
- ⋯ Area boundary
- ⋯ Sale boundary
- ~ Transmission line
- Type-F stream
- Type-N stream
- Unsurfaced road
- Surfaced road
- State highway
- Abandoned road
- Road construction
- County road

EXHIBIT A
 Timber sale contract No. 341-03-17
 Welcomb Ridge
 Sections 1, 2, 11 and 12, T1S, R8W, W. M.
 Tillamook County, Oregon



Area	Acres	
	Sale	Net
1	116	112
2	31	30
Total	147	142

EXHIBIT "B"
FOREST ROAD SPECIFICATIONS

SUBGRADE WIDTH	SURFACED WIDTH	POINT TO POINT	STATION TO STATION	DRAINAGE
14 feet	12 feet	A to B	0+00 to 8+80	Ditch
14 feet	12 feet	A to B	8+80 to 14+75	Outslope
14 feet	12 feet	A to B	14+75 to 17+20	Ditch
14 feet	12 feet	A to B	17+20 to 21+50	Outslope
14 feet	12 feet	A to B	21+50 to 52+80	Ditch
14 feet	12 feet	C to D	0+00 to 14+00	Outslope
14 feet	12 feet	E to F	0+00 to 9+40	Outslope
14 feet	12 feet	G to H	0+00 to 2+40	Ditch
14 feet	12 feet	I to J	0+00 to 8+50	Outslope
14 feet	12 feet	K to L	0+00 to 1+80	Outslope

CLEARING. This work shall consist of clearing, removing, and disposing of all trees, snags, down timber, brush, surface objects, and protruding obstructions within the clearing limits.

Where clearing limits have not been marked, the "Road Brushing Specifications" in Exhibit B shall apply. Clearing debris shall not be placed or permitted to remain in or under any road embankment sections. Clearing debris shall not be left lodged against standing trees.

All danger trees, leaners, and snags outside the clearing limits which could fall and hit the road shall be felled.

GRUBBING. This work shall consist of the removal or digging out of stumps and protruding objects.

All stumps shall be completely removed within the limits of required grubbing. Stumps overhanging cutslopes shall be removed. Grubbing debris shall not be placed or permitted to remain in or under any road embankment sections. Grubbing debris shall not be left lodged against standing trees. Grubbing classifications are as follows:

New construction - From the top of the cutslope to the toe of the fill.

Improvements and reconstructions - 4 feet back from the shoulder of the subgrade or ditch, whichever is widest, or as marked in the field.

CLEARING AND GRUBBING DISPOSAL. Scatter through openings in the timber outside of the cleared right-of-way, except areas where end-haul is required.