

PART III: EXHIBITS

State Timber Sale Contract
No. 341-06-24
Mike Pine

EXHIBIT B

Page 1 of 3
629-Form 341-203
Revised 06/97

OREGON DEPARTMENT OF FORESTRY

TIMBER SALE OPERATIONS PLAN

(See Page 2 for instructions)



Date Received by STATE: _____

(5) State Brand Information (complete):

(1) Contract No.: 341-06-24

(2) Sale Name: Mike Pine

(3) Contract Expiration Date: October 31, 2008

Project Completion Dates: _____

(4) Purchaser: _____

(6) Purchaser Representatives:

Projects: _____

Phone: _____

Cell/Other

Phone: _____

Home: _____

Projects: _____

Phone: _____

Cell/Other

Phone: _____

Home: _____

Projects: _____

Phone: _____

Cell/Other

Phone: _____

Home: _____

Projects: _____

Phone: _____

Cell/Other

Phone: _____

Home: _____

Logging: _____

Phone: _____

Cell/Other

Phone: _____

Home: _____

Logging: _____

Phone: _____

Cell/Other

Phone: _____

Home: _____

Logging: _____

Phone: _____

Cell/Other

Phone: _____

Home: _____

Logging: _____

Phone: _____

Cell/Other

Phone: _____

Home: _____

(7) State Representatives:

Projects: _____

Phone: _____

Cell/Other

Phone: _____

Home: _____

Logging: _____

Phone: _____

Cell/Other

Phone: _____

Home: _____

(8) Name of Subcontractors & Starting Dates:

Projects: No(s) _____ - _____

Date: _____

Phone: _____

No(s) _____ - _____

Date: _____

Phone: _____

No(s) _____ - _____

Date: _____

Phone: _____

No(s) _____ - _____

Date: _____

Phone: _____

Logging: Felling _____

Date: _____

Phone: _____

Yarding: _____

Date: _____

Phone: _____

(9) Comments: _____

(10) Operations Map: Attach a copy of timber sale Exhibit A or other suitable map which plainly shows the items listed on the instruction sheet.

EXHIBIT B

INSTRUCTION SHEET FOR OPERATIONS PLAN

SUBMIT ONE COPY OF PLAN TO STATE

Operations shall be limited to the work shown in the plan until a revised plan or supplemental plan is submitted covering additional work. Compliance with this plan is not in lieu of compliance with any federal requirements related to the federal Endangered Species Act. If STATE has prepared a required Forest Practices Act (FPA) "Written Plan" for operations, PURCHASER shall comply with all provisions of the Written Plan.

Item No. (from Page 1)

- (5) All sales require you to use a brand furnished by STATE. If the State brand has not been assigned when the plan is submitted, it will be furnished and assigned later. Complete drawing. If more than one brand is assigned to the sale, complete both drawings.
- (6) The contract requires you to have a designated representative available on the sale area or work location who is authorized to receive in your behalf any notice or instruction given by STATE and to take action in regard to performance under the contract. If logging and project work is widely separated, a representative is required for each.
- (7) The STATE representative will be designated when your plan is approved and is the person who will inspect and issue instructions regarding performance.
- (8) Show names of subcontractors to be used for any or all phases of the operations. If subcontractors are not known, or are changed later, give notification to the STATE representative prior to commencement of work by subcontractor.

Show projected dates for commencement of both projects and logging. If projected dates need to be changed at a later date, notification must be given to the STATE representative by supplemental plan or otherwise, prior to commencement of such operations.

- (10) The STATE representative will furnish extra copies of Exhibit A of the contract for your use in preparing the operations map. The map shall use the following legend and show:
 1. Landing locations, approximate setting boundaries, and probable sequence of logging the settings. Number the settings in sequence.
 2. Locations of spur roads planned for construction, other than those required by the timber sale contract. Provide spur road specifications.
 3. Location of proposed tractor yarding roads. Show if and how marked on the ground.
 4. Location of temporary stream crossings.
 5. List the sequence of performing project work.
 6. Location of rock sources - attach pit development plans.







	Cable landing, with numbers for sequence.
	Tractor landing with alphabetical sequence.
	Approximate setting boundary.
	Spur truck roads.
	Tractor yarding roads.
	Temporary stream crossings.

EXHIBIT B
OPERATIONS PLAN


Completion Timeline

Indicate on the appropriate timeline below, the dates by which you plan to complete the work as required under this contract. The purpose of this section is to develop a plan that will ensure you complete the work as required, and meet the interim completion date(s) and contract expiration date. This plan is incorporated and made a part of the contract. When, in the opinion of STATE, operations are not commencing in a manner that meets the intent of this plan, you may be placed in violation of contract and your operations suspended until an amended plan is submitted and approved by STATE.

Projects



Harvest & Other Requirements



The Federal Endangered Species Act (ESA) prohibits a person from taking any federally listed threatened or endangered species. Taking under the federal ESA may include alteration of habitat. STATE's approval of this plan does not certify that PURCHASER's operation under the plan is lawful under the federal ESA. As provided in the timber sale contract, PURCHASERS must comply with all applicable state, federal, and local laws.

PURCHASER's compliance with this plan is not in lieu of compliance with any federal requirements related to the federal Endangered Species Act.

APPROVED: Date: _____

SUBMITTED BY:
PURCHASER

STATE OF OREGON - DEPARTMENT OF FORESTRY

Title _____

Title _____

Original: Salem
cc: District File
Purchaser

EXHIBIT C

SCALING INSTRUCTIONS -- LOCATION APPROVAL -- BRAND INFORMATION

(1) ORIGINAL REGISTRATION ☐ Date _____
REVISION NUMBER _____ ☐ Date _____
CANCELLATION ☐ Date _____

(2) TO: _____
(Third Party Scaling Organization)

(3) FROM: Tillamook (06) Phone 503-842-2545
(State Forestry District)
Address 5005 Third Street, Tillamook, OR 97141

(4) PURCHASER: _____
Address _____

(5) MINIMUM SCALING SPECIFICATIONS			CLASS		
SPECIES	SCALING DIAMETER INCHES	*NET SCALE VOLUME	PER MBF	** SUM	SUB
Conifers	--	10	X		
Hardwoods	--	--		X	

* Apply minimum volume test to whole logs over 40' Westside; 20' Eastside.
** Sum (if indicated): see instructions and explain in Item (20).

(6) WESTSIDE SCALE: YES ☒ NO ☐
Actual taper all logs over 40' scaling length

(7) EASTSIDE SCALE: ☐ ☒
*Actual taper butt logs over 40' scaling length

(8) PENCIL BUCK ☐ ☒
back to Minimum Scaling Diameter _____

(9) ADD-BACK VOLUME -- ☒ ☐
Deductions due to delay

(10) APPROVED SCALING LOCATIONS	Species	Yard	Truck

(11) NOTICE OF CANCELLATION OF BRAND:
Effective Date: _____

State Forester's Representative

(12) SALE NAME Mike Pine

COUNTY Tillamook

(13) STATE CONTRACT NUMBER 341-06-24

(14) SCALE: westside ☒ eastside ☐ cubic foot ☐

(15) STATE BRAND REGISTRATION NUMBER _____

(16) BUREAU BRAND CODE NUMBER _____

(17) STATE BRAND INFORMATION:

(COMPLETE) 

(18) PAINT REQUIRED: YES ☒
COLOR Orange

(19) SPECIAL SCALES
PEELABLE CULL (all species)
UTILITY/PULP (all species)
NO DEDUCTIONS ALLOWED FOR MECHANICAL DAMAGE
OTHER: _____
OTHER: _____

(20) REMARKS: Loads containing only SUM material need not be accounted for by scale ticket.

Operator's Name (Optional inclusion by District): _____

(21) SIGNATURES:

Purchaser or Authorized Representative Date

State Forester Representative Date

Notify the District within one hour when branding or painting is inadequate for quick identification, the receipts are missing, not correctly or completely filled out, and/or when logs presented for scaling are impossible to scale accurately.

Distribution: ORIGINAL: Salem / COPIES: TPSO (4), Purchaser, Operator, District, Mgmt. Unit

EXHIBIT C

INSTRUCTIONS FOR FORM 343-307 (rev. 5/01)

- (1) Check appropriate box. REVISION NUMBER requires comments. CANCELLATION requires Item (21). Complete date.
- (2) Designate Third Party Scaling Organization (TPSO). Send 4 copies to TPSO, 1 to purchaser, 1 to Salem, and keep such copies as to district needs.
- (3) State District office, address and phone.
- (4) Enter Purchaser's business name and address as it appears on the Contract.
- (5) Minimum Scaling Specifications. Review Section 2040 or 2045, "Log Removal," of the Contract. Species, or combined species can be separate entries. Information serves as a basis for scaling (see also Items (13) thru (17)), and is required to show existence on the sale. **PerM** (per MBF). **SUM** (lump sum material). **SUB** (submerchantable material. SUB, as used by the State, references that material containing at least 10 bf (net) but less than the lower merchantable net volume limit or grade requirements for other merchantable (PerM) entries. PerM, SUM, and Sub must be indicated by checking the appropriate column. Species with the same specifications and value are combined into one entry. PerM and Sub require scaling therefore complete specifications. SUM need not be scaled, hence no specifications. Loads containing only SUM are to be ticketed if so instructed in Item (19). Mixed loads of SUM, PERM and/or subspecies will always be scaled.
- (6) Westside -- actual taper segment scale. Check Yes or No. Special Service Rules on file with TPSO. See: Segment Scaling and Grading of Long Logs -- All Species -- State Forestry Department Scaling Practices (Westside).
- (7) Eastside -- actual taper/taper table segment scale. Special Service Rules on file with TPSO. See: Segment Scaling and Grading of Long Logs -- All Species -- State Forestry Department Scaling Practices (Eastside). Items with * follow U.S. Forest Service Eastside rules.
- (8) Pencil Buck. Check NO if a westside sale, optional for eastside sales.
- (9) Add-Back Volume. Add-Back is normally checked YES. Scaler records deductions (sap rot, weather checks, etc.) caused by an abnormal delay in removal. Enter separately on scale ticket. TPSO provides State with summaries that include this as a net volume by species. Salvage sales and certain other circumstances may require that "NO" be checked.
- (10) Show scaling locations only applicable to TPSO. Not necessary to list markets. If all species are scaled at same location, enter "ALL."
- (11) When logging is complete, recall branding hammers, date and sign where indicated, check CANCELLATION box at top of form, and send to TPSO.
- (12) Enter sale name and county.
- (13) Enter sale Contract number.
- (14) Check Westside or Eastside log scale. Cubic foot refers to Northwest Log Rules Cubic Foot Scale.
- (15) Oregon Forest Products Brand Registry Number (optional).
- (16) DO NOT USE -- TPSO will fill in when applicable.
- (17) Show one brand only. Complete drawing. If more than one brand is assigned to the sale, (1) make separate form for each brand, and (2) on each form, explain and show other brand(s) under REMARKS, Item 19.
- (18) Check YES and designate orange.
- (19) Special Scales. These are the Special Scales that will be applied. If "Other" is indicated, please describe. Give comments in Item (19).
- (20) Use this space to designate weight conversion factors, or any other explanations to clarify scaling requirements. If additional scaling locations are approved, prepare another form showing all (old and new) locations. Check REVISION box at top of form and explain under remarks. Route as indicated.
- (21) Require purchaser to sign and date completed form.

EXHIBIT D
FOREST ROAD SPECIFICATIONS

SUBGRADE WIDTH	SURFACED WIDTH	POINT TO POINT	STATION TO STATION	DRAINAGE	TOP DITCH WIDTH (Feet)	DITCH CONFIGURATION (U, V, TRAPEZOID)	DITCH DEPTH FROM FINISHED SURFACE (Feet)	DITCH DEPTH FROM SUBGRADE (Feet)
14 feet	12 feet	A to B	0+00 to 59+90	Ditch	3	V	1.5	---
14 feet	12 feet	A to B	59+90 to 111+50	Outslope	---	---	---	---
14 feet	12 feet	A to B	111+50 to 111+85	Ditch	*	Trapezoid	---	2
14 feet	12 feet	A to B	111+85 to 136+55	Outslope	---	---	---	---
14 feet	12 feet	A to B	136+55 to 137+10	Ditch	*	Trapezoid	---	2
14 feet	12 feet	A to B	137+10 to 169+55	Outslope	---	---	---	---
14 feet	12 feet	C to D	0+00 to 19+70	Outslope	---	---	---	---
14 feet	12 feet	E to F	0+00 to 10+05	Outslope	---	---	---	---
14 feet	12 feet	E to F	10+05 to 25+10	Ditch	3	V	---	1.5
14 feet	12 feet	E to F	25+10 to 43+55	Outslope	---	---	---	---
14 feet	12 feet	G to H	0+00 to 55+10	Ditch	3	V	1.5	---
14 feet	12 feet	I to J	0+00 to 25+25	Outslope	---	---	---	---
14 feet	12 feet	K to L	0+00 to 34+55	Ditch	3	V	---	1.5
14 feet	12 feet	M to N	0+00 to 8+25	Ditch	3	V	---	1.5
14 feet	12 feet	O to P	0+00 to 45+80	Ditch	3	V	1.5	---

* Top of ditch width shall be 7 feet and ditch bottom width shall be 3 feet.

EXHIBIT D
FOREST ROAD SPECIFICATIONS

CLEARING. This work shall consist of clearing, removing, and disposing of all trees, Snags, Down Timber, brush, surface objects, and protruding obstructions within the clearing limits.

Where clearing limits have not been marked, the "Road Brushing Specifications" in Exhibit D shall apply. Clearing debris shall not be placed or permitted to remain in or under any road embankment sections. Clearing debris shall not be left lodged against standing trees.

All danger trees, leaners, and Snags outside the clearing limits which could fall and hit the road shall be felled.

GRUBBING. This work shall consist of the removal or digging out of stumps and protruding objects.

All stumps shall be completely removed within the limits of required grubbing. Stumps overhanging cutslopes shall be removed. Grubbing debris shall not be placed or permitted to remain in or under any road embankment sections. Grubbing debris shall not be left lodged against standing trees. Grubbing classifications are as follows:

New construction - From the top of the cutslope to the toe of the fill.

Improvements and reconstructions - 4 feet back from the shoulder of the subgrade or the ditch, whichever is widest, or as marked in the field.

Trees outside the clearing limits shall not be felled unless approved in writing by STATE.

Sidecast pullback – From top of pullback to toe of pullback.

CLEARING AND GRUBBING DISPOSAL. Scatter through openings in the timber outside of the cleared right-of-way, except areas where end-haul is required.

EXHIBIT D

FOREST ROAD SPECIFICATIONS

EXCAVATION. Excavation and grading shall not be done when weather and/or ground conditions are such that damage will result to existing subgrade or cause excessive erosion.

Excavation shall conform to STATE-engineered lines, grades, dimensions, and plans when provided.

All suitable excavated material shall be used where possible for the formation of fills, shoulders, and drainage structure backfills. Embankment materials shall be free of woody debris, brush, muck, sod, frozen material, and other deleterious materials. All fills and drainage structure backfills shall be machine compacted according to the specifications in Exhibits E and G.

Unless road design plans show otherwise, all roads shall be on a balanced cross section, except when the slope is over 50 percent, the road shall be on full bench for the width specified.

Excess excavation shall not be sidecast where material will enter a stream course or where material will accumulate in areas deemed a high landslide hazard location by STATE.

Bank excavation and sidecast pullback on a project road segment shall be completed prior to subgrade approval.

ROAD WIDTH LIMITATIONS. PURCHASER shall obtain advance written approval from STATE to construct the road to a greater width than specified. Extra subgrade width shall be required for:

Fill Widening. Add to each fill shoulder 1 foot for fills 3 feet to 6 feet high; 2 feet for fills over 6 feet high.

Curve Widening. Widen the inside shoulder of all curves as follows: 400 divided by the radius of the curve equals the amount of extra width.

DRAINAGE

Ditch. Construct ditch as specified in Exhibit D. Subgrade shall be crowned at 4 to 6 percent. Construct ditchouts away from subgrade at locations specified in Exhibit D and as marked in the field. All through-cuts on ditched road segments shall have a ditch on both road edges.

Outslope. Road subgrade shall be outsloped at 4 to 6 percent. Construct ditchouts away from subgrade at locations specified in Exhibit D and as marked in the field. All through-cuts on outsloped road segments shall have a ditch on the lower outsloped road edge only.

TURNOUTS. Increase roadbed width an additional 8 feet for both subgrade and surfacing. Length shall be at least 25 feet, or as staked on the ground, plus 25-foot approaches at each end.

Location: As marked in the field.

GRADING

Back Slopes

Fill Slopes

Rock

Vertical to 1/4:1

Not steeper

Common -

3/4:1

than 1 1/2:1

Common - turnpike (level) section

2:1

Top of cutslope shall be rounded.

TURNAROUNDS. Increase subgrade width an additional 30 feet for a length of 16 feet with 20' radius returns at locations marked in the field.

JUNCTIONS. Increase roadbed width as marked in the field.

EXHIBIT D

ADDITIONAL ROAD INSTRUCTIONS

A to B:

- Construct road dips at Stations 74+90, 76+55, 77+95, 81+40, 88+95, 93+50, 94+80, 111+50, 112+70, 115+25, 117+20, 120+70, 127+30, 129+85, 133+40, 138+40, 143+05, 145+60, 150+30, 153+55, and 164+80 according to the specifications in Exhibit H.
- Retrieve log cribbing and sidecast material between Stations 94+25 and 94+65 according to the specifications in Exhibit I, and as marked in the field. Place logs perpendicular to roadway outside of right-of-way on fill slope side.
- Widen road subgrade width 3 feet to the left between Stations 90+55 to 92+10 and 102+10 to 103+55.
- Widen road subgrade width 4 feet to the left between Stations 72+40 to 74+10 and 80+95 to 83+45.
- Widen road subgrade width 6 feet to the left between Stations 98+25 and 99+55.
- Construct a ditchout to the right at Stations 56+75, 61+05, 63+50, 65+15, 68+70, 71+70, 75+75, 85+40, 96+85, and 157+00.
- Remove logs and fill in stream channel between Stations 31+45 to 31+85 and 73+10 to 73+55 and reconstruct fill according to the specifications in Exhibits E and G. Place logs perpendicular to roadway outside of right-of-way on fill slope side.
- Repair fill slope failure between Stations 112+60 and 112+80 according to the specifications in Exhibits E and L.
- Remove existing half-rounds from STATE land on side of road at Station 45+05.
- Repair culvert inlet at Stations 24+00 and 45+95.
- Remove berm on outside edge of road to a slope of at least 4 to 6 percent, away from the road, between Stations 157+00 and 166+85.

C to D:

- Remove logs and fill in stream channel between Stations 8+15 and 8+35 and reconstruct fill according to the specifications in Exhibits E and G. Place logs perpendicular to roadway outside of right-of-way on fill slope side.

E to F:

- Construct road dips at Stations 4+00 and 40+05 according to the specifications in Exhibit H.
- Construct a ditchout to the left at Stations 14+40 and 17+05.
- Construct a ditchout to the right at Stations 19+00, 25+10, 42+20, 34+30, and 39+20.
- Remove berm on outside edge of road to a slope of at least 4 to 6 percent, away from the road, between Stations 1+80 to 4+00 and 25+10 to 42+05.

EXHIBIT D

ADDITIONAL ROAD INSTRUCTIONS (cont.)

G to H:

- Construct a ditchout to the left at Stations 3+45, 17+70, and 31+30.
- Construct a ditchout to the right at Stations 47+55 and 49+45.
- Repair culvert inlet at Station 19+70.

I to J:

- Remove berm on outside edge of road to a slope of at least 4 to 6 percent, away from the road, between Stations 0+00 to 3+25 and 4+75 to 15+20.
- Construct road dips at Stations 4+75, 9+10, and 12+80 according to the specifications in Exhibit H.
- Raise subgrade elevation to establish a constant road grade between marked subgrade elevations at Stations 19+65 and 20+70

K to L:

- Construct a ditchout to the left at Stations 10+95, 15+80, 19+65, and 21+65.
- Construct a ditchout to the right at Station 22+90.


M to N:

- Construct a lead-off ditch away from culvert outlet at Station 0+35.
- Construct a ditchout to the right at Station 7+00.
- Remove berm on outside edge of road to a slope of at least 4 to 6 percent, away from the road, between Stations 4+00 and 8+25.

O to P:

- Remove existing culvert from STATE land and backfill trench with pit-run material at Station 0+00.

EXHIBIT D
ROAD BRUSHING SPECIFICATIONS



REQUIREMENTS

Unless otherwise approved in writing by STATE, brush and trees shall be cut to a height of 6 inches or less above the ground surface or obstructions such as rocks or existing stumps. Brushing on project road segments shall be completed prior to subgrade approval.

Debris resulting from the brushing operation shall be removed from the roadway, cutslope, ditches, and water courses within 72 hours and may be scattered downslope from the road or placed in other stable locations, unless otherwise approved by STATE.

Trees outside the clearing limits shall not be felled unless approved in writing by STATE.

EXHIBIT D

END-HAULING REQUIREMENTS

POINT TO POINT	STATION LOCATION	WASTE AREA LOCATION	WASTE AREA TREATMENT
A to B	16+75 to 16+95, 31+45 to 31+85, 72+40 to 74+10, 80+95 to 83+45, 90+55 to 92+10, 94+25 to 94+65, 98+25 to 99+55, 102+10 to 103+55, 111+50 to 111+85, 136+55 to 137+10, and 164+80 to 166+85	1	1
K to L	0+00 to 5+25, 8+00 to 12+35, and 25+55 to 28+50	2 and 3	2
K to L	12+35 to 17+05	1 and 4	1 and 2
M to N	4+00 to 8+25	1	1
O to P	0+00 to 0+30	1	1

End-Haul Areas General Requirements

Material shall not be intentionally side cast.

Clearing and grubbing debris shall be end-hauled.

When blasting is required, it shall be accomplished using timing devices, delayed charges, low intensity shots, or other suitable means to contain all material within the road prism.

Containment

Full containment: The amount of material lost over the outside edge of the road shall not exceed 6 inches in depth measured perpendicular to the natural ground slope. Pioneer excavation shall be removed by digging, loading, and hauling rather than by pushing or scraping methods.

Tree bases and stumps may have up to 12 inches of material directly above them. Any amount of material exceeding the containment requirements shall be removed by whatever means necessary and end-hauled to a designated waste area.

Waste Area Location

- (1) As shown on Exhibit A and as marked in the field.
- (2) On Road Segment K to L (Stations 5+25 to 12+35).
- (3) On Road Segment K to L (Stations 20+75 to 25+55).
- (4) On Road Segment K to L (Stations 30+80 to 34+55).

Waste Treatment

- (1) Deposit at waste area, spread evenly, compact, and provide adequate drainage. Pile woody debris separate from other waste material.
- (2) Suitable material shall be used for fill construction.

EXHIBIT E
ROAD SURFACING

Note: The conversion from compacted yardage to truck yardage is 1.2 multiplied by the compacted yardage equals truck yardage.

TYPE OF ROCK	SIZE OF ROCK	COMPACTED DEPTH	POINT TO POINT	STATION TO STATION	APPROX. TOTAL TRUCK MEASURE VOLUME
Crushed	2"-0"	3"	A to B	124+80 to 153+55	417 CY*
Pit-Run	---	12"	A to B	51+90 to 153+55	6435 CY
Pit-Run	---	9"	A to B	153+55 to 169+55	739 CY
Pit-Run	---	9"	C to D	0+00 to 19+70	896 CY
Crushed	2"-0"	3"	E to F	1+80 to 4+00	44 CY*
Crushed	2"-0"	3"	E to F	10+05 to 25+10	217 CY*
Pit-Run	---	12"	E to F	0+00 to 43+55	3012 CY
Crushed	2"-0"	3"	I to J	0+00 to 3+25	60 CY*
Pit-Run	---	9"	I to J	0+00 to 25+25	1201 CY
Crushed	2"-0"	3"	K to L	0+00 to 34+55	497 CY*
Pit-Run	---	9"	K to L	0+00 to 34+55	1583 CY
Pit-Run	---	9"	M to N	0+00 to 8+25	374 CY
Crushed	2"-0"	3"	O to P	0+00 to 0+30	8 CY*
Pit-Run	---	9"	O to P	0+00 to 0+30	26 CY
TURNOUTS:			NO. OF T.O.	LOCATION	
Crushed	2"-0"	3"	3	A to B: 124+80, 128+10, and 135+70	14 CY*
Pit-Run	---	12"	13	A to B: 10+35, 30+90, 45+05, 50+85, 58+80, 70+35, 78+50, 95+65, 101+90, 107+40, 124+80, 128+10, and 135+70	264 CY
Pit-Run	---	9"	1	A to B: 157+00	15 CY
Crushed	2"-0"	3"	2	E to F: 10+05 and 17+05	9 CY*
Pit-Run	---	12"	3	E to F: 10+05, 17+05, and 33+00	61 CY
Pit-Run	---	9"	3	G to H: 16+85, 29+55, and 37+30	44 CY

EXHIBIT E
ROAD SURFACING

TYPE OF ROCK	SIZE OF ROCK	COMPACTED DEPTH	NO. OF T.O.	LOCATION	APPROX. TOTAL TRUCK MEASURE VOLUME
TURNOUTS:					
Pit-Run	---	9"	2	I to J: 6+35 and 19+65	30 CY
Crushed	2"-0"	3"	4	K to L: 3+00, 10+65, 21+80, and 31+40	18 CY*
Pit-Run	---	9"	4	K to L: 3+00, 10+65, 21+80, and 31+40	59 CY
TURNAROUNDS:			NO. OF T.A.		
Crushed	2"-0"	3"	2	A to B: 134+85 and 150+90	15 CY*
Pit-Run	---	12"	5	A to B: 4+85, 88+15, 97+40, 134+85, and 150+90	161 CY
Pit-Run	---	9"	1	A to B: 169+55	24 CY
Pit-Run	---	9"	2	C to D: 2+50 and 19+70	47 CY
Pit-Run	---	12"	1	E to F: 31+20	32 CY
Crushed	2"-0"	3"	1	I to J: 3+25	7 CY*
Pit-Run	---	9"	2	I to J: 3+25 and 15+20	48 CY
Crushed	2"-0"	3"	1	K to L: 33+80	7 CY*
Pit-Run	---	9"	1	K to L: 33+80	24 CY
Pit-Run	---	9"	1	M to N: 8+25	24 CY
JUNCTIONS:			NO. OF JUNC.		
Crushed	2"-0"	3"	1	A to B: 153+55	5 CY*
Pit-Run	---	12"	8	A to B: 0+00, 6+15, 20+30, 51+90, 59+90, 112+70, 118+85, and 153+55	160 CY
Crushed	2"-0"	3"	1	E to F: 23+70	5 CY*
Pit-Run	---	12"	1	E to F: 23+70	20 CY
Crushed	2"-0"	3"	1	G to H: 45+30	5 CY*
Pit-Run	---	9"	1	G to H: 45+30	15 CY

EXHIBIT E
ROAD SURFACING

TYPE OF ROCK	SIZE OF ROCK		USE	LOCATION	APPROX. TOTAL TRUCK MEASURE VOLUME
MISCELLANEOUS:					
Crushed	2"-0"	---	Culvert Bedding/ Backfill	A to B: 73+35	20 CY
Pit-Run	---	---	Backfill	A to B: 16+85, 31+65, 49+00, 73+35, and 137+10	70 CY
Pit-Run	---	---	Leveling Rock	A to B: 81+40 – 82+25 and 93+50 – 94+25	100 CY
RipRap	24"-12"	---	Energy Dissipater/ Slope Stabilization	A to B: 24+00, 73+35, 112+70, and 137+10	35 CY
Crushed	2"-0"	---	Culvert Bedding/ Backfill	C to D: 8+25	15 CY
Pit-Run	---	---	Backfill	C to D: 8+25	10 CY
Pit-Run	---	---	Backfill	E to F: 14+40, 20+30, and 25+10	30 CY
Pit-Run	---	---	Backfill	K to L: 10+60, 18+90, 25+25, and 28+50	40 CY
Pit-Run	---	---	Backfill	M to N: 0+35 and 2+85	20 CY
Pit-Run	---	---	Backfill	O to P: 0+00 and 0+30	20 CY

* Obtain approval from STATE for Pit-Run rocking prior to spreading crushed rock.

Roads shall be uniformly graded and approved by STATE prior to rocking.

Additional rock for curve widening is required and has been included in the volume estimates.

Turnouts, turnarounds, and junctions shall be rocked concurrently with the road.

End-dumping of riprap shall not be allowed, unless otherwise approved in writing by STATE.

For typical cross section, turnout and turnaround, see Forestry Department Drawing Nos. 351-C, 351-D and TOTA-1 at the Forestry Department District Office.

EXHIBIT E
ROCK SPECIFICATIONS

Materials. The material shall be fragments of rock or other hard, durable particles crushed to the required size and a filler of finely crushed stone, sand, or other finely divided mineral matter. The material shall be free from vegetation and lumps of clay.

Quality and Grading Requirements. The stone base materials shall be crushed rock, including sand.

River gravel shall not be used.

The material from which base material is produced or manufactured shall meet the following test requirements:

Hardness - Test Method AASHTO T 96 35% Maximum

Durability - Test Method ODOT TM 208
Passing No. 20 Sieve: 30% Maximum
Sediment Height: 3" Maximum

<u>For 6"-0" Pit-Run</u>	Passing	10" sieve	100%
	Passing	6" sieve	60-85%
	Passing	3" sieve	30-50%
	Passing	¼ " sieve	10% maximum

48"-4" Riprap 50% or more of the rock shall be at least one cubic yard in volume. 100% of the rock shall be at least four cubic feet in volume.

Control of riprap and pit-run gradation shall be by visual inspection by STATE. Pit run shall be reasonably free of organic material and shall not contain an excessive amount of oversized (cobbles or boulders) or undersized (clay, silt or sand) particles.

The referenced sieve shall have square openings as set forth in AASHTO M 92, Woven Cloth Series. The determinations of size and gradings shall be as set forth in AASHTO T 27.

EXHIBIT E

ROCK ACCOUNTABILITY

Purchaser shall obtain STATE approval for subgrades prior to rocking. Rocking must be done only when weather conditions are acceptable to STATE, and must be suspended when muddy water could enter streams.

Rock accountability shall be determined by the following methods, as directed by STATE. STATE shall be given 24 hours' notice prior to rocking.

Depth Measurement. Road rock shall be spread and compacted according to the depths specified in Exhibit E. Truck measure volumes are given, but shall not limit the amount of rock spread.

Depth shall be determined in the most compacted area of the surface cross section. If additional rock is required because of insufficient depth, it shall be added by truck measure to those areas that were slighted. The conversion from compacted yardage to truck yardage is 1.2 multiplied by the compacted yardage equals truck yardage.

The depth of compacted aggregates shall not vary more than 1 inch from the depth specified in Exhibit E. The average depth for each road segment shall be the specified depth or greater.

Junctions shall have a surfaced area as marked in the field at the compacted depths specified in Exhibit E.

Turnouts shall have a surfaced area of at least 44 square yards each at the depths shown in Exhibit E.

Turnarounds shall have a surfaced area of at least 73 square yards each at the depths shown in Exhibit E.

Curve Surfacing. Extra surface width shall be required for the inside of all curves as follows: 400 divided by the radius of the curve equals the amount of extra width to be surfaced at the depths shown in Exhibit E.

EXHIBIT E

COMPACTION AND PROCESSING REQUIREMENTS

Subgrade. Subgrade surfaces of the road segments listed below shall be graded and compacted prior to rocking. Compaction shall be accomplished by traveling all surfaces from shoulder to shoulder until visible deformation ceases, or in the case of a sheepsfoot roller, the roller "walks out." At least 3 passes shall be made over the entire width and length of the road. A pass is defined as traveling a road section in one direction and then back over that same section again. Compaction shall be accomplished by using the approved equipment listed below or others approved by STATE.

ROAD SEGMENT	COMPACTION EQUIPMENT OPTIONS
All	Vibratory Roller

Proof-rolling. Prior to placing the road rock surfacing, PURCHASER shall proof-roll the compacted subgrade of the road segments listed below with a rock truck loaded with a least 10 cubic yards of soil and approved by STATE. Proof-rolling shall consist of at least two complete passes with one pass being in the opposite direction to the preceding one. To obtain subgrade approval, PURCHASER shall perform proof-rolling when STATE is present. PURCHASER shall notify STATE a minimum of 48 hours prior to beginning proof-rolling. Areas that deflect, rut, or pump more than two inches during proof-rolling shall be corrected prior to placing the road rock surfacing. Subgrade shall be maintained until succeeding operation has been accomplished.

ROAD SEGMENT	STATION TO STATION	COMPACTION EQUIPMENT OPTIONS
A to B	51+90 to 169+55	Rock Truck

Fills. Embankments and fills shall be placed in (approximately) horizontal layers not more than 8 inches in depth. Each layer shall be separately, and thoroughly, compacted. Compaction equipment shall be operated over the entire width of each layer until visible deformation of the layers ceases or, in the case of a sheepsfoot roller, the roller "walks out." At least 3 passes shall be made over the entire width and length of each layer. A pass is defined as traveling a fill layer in one direction and then back over that same layer again.

Placing individual rocks or boulders with more depth than the allowed layer thickness shall be permitted, provided the embankment will accommodate them. Such rocks and boulders shall be at least 6 inches below the subgrade. They shall be carefully distributed and the voids filled with finer material, forming a dense and compacted mass. Compaction shall be accomplished by using the approved equipment listed below or others approved by STATE:

ROAD SEGMENT	COMPACTION EQUIPMENT OPTIONS
All	Tampingfoot Compactor

EXHIBIT E

COMPACTION AND PROCESSING REQUIREMENTS

Pit-Run Rock. Pit-run surfacing rock shall be spread on roads with a crawler tractor and continuously walked-in. Rock spreading shall begin at nearest point from the rock source and progress toward the end of the project, unless otherwise approved in writing by STATE. Compaction shall be accomplished by using the approved equipment listed below or others approved by STATE:

Rock shall be compacted and processed during the same project period it is spread, unless otherwise approved in writing by STATE.

Rock shall be crowned or outsloped at 4 to 6 percent unless otherwise specified.

ROAD SEGMENT	COMPACTION EQUIPMENT OPTIONS
All	Vibratory Grid Compactor

Crushed Rock. The rock shall be uniformly mixed and spread in layers on the approved roadbed. Each layer of crushed rock shall be moistened or dried to a uniform moisture content suitable for maximum compaction and compacted in layers not to exceed 6 inches in depth. When more than 1 layer is required, each shall be shaped and compacted before the succeeding layer is placed. Any irregularities or depressions that develop during compaction of the top layer shall be corrected by loosening the material at these places and adding or removing material until the surface is smooth and uniform. Each layer shall be compacted with a minimum of 3 passes over the entire width and length of the road. A pass is defined as traveling a road section in one direction and then back over that same section again. Compaction shall be accomplished by using the approved equipment listed below or others approved by STATE:

Rock shall be compacted and processed during the same project period it is spread, unless otherwise approved in writing by STATE.

Rock shall be crowned at 4 to 6 percent unless otherwise specified.

ROAD SEGMENT	COMPACTION EQUIPMENT OPTIONS
All	Vibratory Roller

EXHIBIT E

COMPACTION EQUIPMENT OPTIONS

Vibratory Rollers. The drum shall have a smooth surface, a diameter not less than 48 inches, a width not less than 58 inches, and a turning radius of 15 feet or less. Vibration frequency shall be regulated in steps to 1400, 1500, and 1600 VPM, corresponding to engine speeds of 1575, 1690, and 1800 RPM. The centrifugal force developed shall be 7 tons at 1600 VPM. It shall be activated by a power unit of not less than 25 horsepower. The vibratory roller shall be self-propelled and operated at speeds ranging from 0.9 mile to 1.8 miles per hour, as directed by STATE.

Tampingfoot Compactors. Tampingfoot or sheepsfoot compactors shall exert a minimum pressure of 250 pounds per square inch on the ground area in contact with the tamping feet. The compactor shall cover a minimum width of 60 inches per pass and weigh a minimum of 16,000 pounds.

Vibratory Grid Compactors. The roller shall have a grid surface and have an operating weight of 32,000 pounds or more. The rock shall be worked with a grader weighing at least 20,000 pounds during the grid rolling process. All rock shall come in contact with the vibratory grid compactor. A minimum of 10 passes shall be made with the grader and vibratory grid compactor over the entire length of the road, unless STATE requires fewer passes.

Rock Trucks. Rock spreading shall begin at the nearest point to the rock source and progress toward the end of the project. Rock trucks shall be routed over the entire cross section of rock layers.

EXHIBIT F

ROCK PIT DEVELOPMENT AND USE

- (1) PURCHASER shall conduct the Operations relative to the disposal of waste material in such manner that silt, rock, debris, dirt, or clay shall not be washed, conveyed, or otherwise deposited in any stream. All waste shall be deposited at an approved "waste disposal site."
- (2) Where overburden removal limits have not been marked, they shall extend for a distance of at least 20 feet beyond the developed rock source. Overburden removal limits, when marked, are designated by orange right-of-way boundary tags. Overburden and woody debris shall be hauled to a designated waste area. All merchantable timber shall be felled and decked. Overburden shall be spread evenly, grass seeded, and compacted at the waste area and woody debris stacked separately. Prior to drilling or rock removal, completion of overburden removal shall be approved in writing by STATE.
- (3) The rock pit floor shall be developed to provide drainage away from the rock pit. Rock pit drainage ditches shall be developed and maintained. Benches shall be constructed at intervals of 40 feet or less in height and shall be a minimum of 20 feet in width. Any gravel or talus slopes shall be left with a working face at an angle of 60 degrees or less. There shall be a minimum of 1 bench with an access road to it. All benches shall have an access road to them. Said benches shall be easily accessible with tractors.
- (4) Controlled blasting techniques shall be utilized for any blasting operations, and shall be accomplished using timing devices, delayed charges, low intensity shots, or other suitable means to contain all material in the rock pit prism (full containment). Each low intensity shot shall be shot into the previous shots' void in order to contain all the material in the rock pit prism. Each shot shall also have a "tattle-tale" end cap so that it is known if all charges were detonated. The purchaser shall detonate or remove all non-detonated explosives from STATE LANDS. PURCHASER shall maintain a comprehensive log that contains all pertinent data for all blasting operations. The blasting log shall be submitted to the STATE after the completion of all blasting activity. The blasting log is intended for STATE record keeping purposes only.
- (5) Pit face shall be developed in a uniform manner.
- (6) Oversized material that is produced shall be piled in the vicinity of the pit. It shall not be wasted.
- (7) PURCHASER shall prepare a written development plan for the pit area. The plan shall be submitted to STATE for approval prior to conducting any operation in the pit area.

The plan shall include, but not be limited to:

- (a) Location of benches and roads to benches.
 - (b) Disposal site for debris and overburden.
 - (c) Time lines for rock quarry use.
 - (d) Erosion control measures.
 - (e) Oversized material location.
- (8) PURCHASER shall schedule and coordinate quarry and stockpile usage with other existing or planned STATE contracts requiring quarry and stockpile usage.
 - (9) PURCHASER shall notify STATE 5 days prior to the start of quarry development activities.
 - (10) Upon completion of use, the pit site and access roads shall be left in a condition free from overburden and debris. Rock pit roads shall be waterbarred to provide drainage as specified in Exhibit H and blocked as directed by STATE.

EXHIBIT G

CULVERT SPECIFICATIONS

All culvert materials shall be furnished and installed by PURCHASER, unless otherwise specified in the Contract. Culverts shall be constructed of corrugated polyethylene. Culverts shall conform to the material and fabricating requirements of the "Standard Specifications for Highway Construction" prepared by the Highway Division of the Oregon State Department of Transportation. Polyethylene culverts shall also be double walled and meet the requirements of AASHTO M-294-901, Type S. Corrugation types and shapes other than those meeting the above minimum Highway requirements, shall be approved in writing by STATE.

Culverts shall be located according to the alignment and grade as shown on the Plan and Profile, and/or as staked in the field, or as stipulated in special instructions.

The STATE Representative shall determine final culvert locations and stake the locations in the field prior to installation.

Culvert grade shall slope away from ditch grade at least 5 percent unless otherwise specified.

The foundation and trench walls for all culverts shall be free from logs, stumps, limbs, stones, and other objects which would dent or damage the pipe. The culvert trench shall be excavated 3 pipe diameters wide to permit compaction and working on each side of the pipe. Tamping shall be done in 6-inch lifts, 1 pipe diameter each side of the pipe to 95 percent density or over. Bedrock shall be excavated as required to provide a uniform foundation for the full length of the culvert. Minimum bedding depth shall be 6 inches.

A bedding of granulated material or crushed rock as specified shall be placed to provide a wide band of support and to transmit the load from above evenly over the entire length of the pipe.

Backfill shall consist of granulated material, crushed rock, or job-excavated soil free of stumps, limbs, rocks, or other objects which would damage the pipe.

Transporting of the pipe shall be done carefully. Dragging or allowing free fall from trucks or into trenches shall not be permitted.

Polyethylene joints shall be made with split couplings, corrugated to engage the pipe corrugations, and shall engage a minimum of 4 corrugations, 2 on each side of the pipe joint.

A manufacturer's certification that the product was manufactured, tested, and supplied in accordance with this specification shall be furnished to the Project Engineer upon request.

EXHIBIT G

CULVERT SPECIFICATIONS

Minimum height of cover over top of culvert to subgrade when road is to be rocked shall be as follows: 12" for culverts 18" to 36" in diameter (add 6" for roads which will not be rocked). Minimum vertical cover for other designs shall be as specified by STATE.

Lengths of individual culvert sections shall be not less than 10 feet, unless otherwise provided for in special instructions.

The ends of each culvert shall be free of logs and debris which would restrict the free flow of water. The intake end of relief culverts shall be provided with a sediment catching basin 3 feet in diameter at the bottom. The outlet end of any culvert which would allow water to erode embankment soil shall be provided with an approved slope protection device. Construct lead-off ditches away from culvert outlets where the slope gradients restrict the free flow of water.

EXHIBIT G
CULVERT LIST

CULVERT NO.	DIAMETER (Inches)	LENGTH (Feet)	ROAD SEGMENT POINT TO POINT	STATION
1	18	32	16+85	A to B
2	18	32	31+65	A to B
3	18	38	49+00	A to B
4	30	40	73+35	A to B
5	18	34	137+10	A to B
6	18	28	14+40	E to F
7	18	28	20+30	E to F
8	18	32	25+10	E to F
9	18	36	10+60	K to L
10	18	28	18+90	K to L
11	18	38	25+55	K to L
12	18	28	28+50	K to L
13	18	32	0+35	M to N
14	18	30	2+85	M to N
15	18	32	0+30	O to P

The intake end of culverts shall be marked by installing a 5 foot long, painted steel fence post two feet into the ground, within 6 inches of the inlet on the downgrade side.

Tamping is required on all culverts. Backfills on culverts over 24 inches in diameter shall be compacted with a vibratory hand-operated or backhoe mounted tamper. The tamper shoe dimensions shall be a minimum of 10" X 13" and capable of a centrifugal force of 2,250 pounds.

All culverts scheduled for replacement shall become property of PURCHASER and be removed from State land in the same project period in which replacement occurred.

EXHIBIT G

TYPICAL EMBEDDED ENERGY DISSIPATOR








EXHIBIT H
 WATERBAR SPECIFICATIONS



**WATERBAR SPECIFICATIONS
 FOR CROSS DITCHING #298**

EXHIBIT H

ROAD DIP CONSTRUCTION SPECIFICATIONS



DIMENSIONS

ROAD GRADE %	A	B
0% - 5%	50'	1.0'
5% - 10%	60'	1.5'
10% - 15%	70'	2.0'
MORE THAN 15%	USE WATERBARS	

ROAD DIP CONSTRUCTION SPECIFICATIONS

SCALE: NOTED	APPROVED BY:	DRAWN BY FB
DATE: 10/14/80		REVISED
STATE OF OREGON DEPARTMENT OF FORESTRY 2600 STATE STREET SALEM OREGON 97310		
		DRAWING NUMBER 669

EXHIBIT I
TYPICAL SIDECAST PULLBACK




EXHIBIT J

SEEDING AND FERTILIZING

This work shall consist of preparing seedbeds and furnishing and placing required seed and fertilizer.

Seeding Seasons. Seeding shall be performed only from March 1 through June 15 and August 15 through October 15. Seeding materials shall not be applied during windy weather or when the ground is excessively wet or frozen. Areas of disturbed soil shall be seeded by the end of the project period in which work was started. PURCHASER shall notify STATE 24 hours prior to seeding.

Soil Preparation. Areas to be seeded that have been damaged by erosion or other causes shall be restored prior to seeding. All areas to be seeded shall be finished and then cultivated to provide a reasonably firm, but friable seedbed. A minimum of 1/2 inch of surface soil shall be in a loose condition.

Application Methods for Seed and Fertilizer

Dry Method. Mechanical seeders, seed drills, landscape seeders, cultipacker seeders, fertilizer spreaders or other approved mechanical seeding equipment shall be used to apply the seed and fertilizer in the amounts and mixtures specified. Hand-operated seeding devices may be used when seed and fertilizer are applied in dry form.

Application Rates for Seed and Fertilizer

Seed listed below shall be applied at the following rates per acre:

<u>Species</u>	<u>Lb./Acre</u>	<u>Mixture</u>	<u>Pure Live Seed</u>	<u>Poison and/or Repellent</u>
Fine Fescue	12	40%	98%	0
Annual Ryegrass	6	20%	98%	0
Perennial Ryegrass	9	30%	98%	0
White Dutch Clover	3	10%	98%	0

Fertilizer: Chemical analysis shall be 16-20-0 and shall be applied at the rate of 300 pounds per acre.

Seeding will be considered acceptable when all other specified requirements in Exhibits J and K have been completed and a healthy, uniform, close stand of grass has been established, unless otherwise approved in writing by STATE.

State Timber Sale Contract
No. 341-06-24
Mike Pine

EXHIBIT K

MULCHING

This work shall consist of furnishing and placing required mulch. Mulch shall consist of straw that is free of noxious weeds.


Mulching Period. Straw mulch shall be applied within 24 hours of spreading grass seed and fertilizer.

Application Rates for Mulch

Place straw mulch to a reasonably uniform thickness of $\frac{3}{4}$ to $1\frac{1}{4}$ inches. This rate requires between 1 and $1\frac{1}{2}$ tons of dry mulch per acre.

EXHIBIT L

FILL SLOPE STABILIZATION
NTS



ALL ROCKS TO BE SOUND, UNWEATHERED ANGULAR ROCK. PRIMARY ROCK SHALL BE 500-3000 LBS AND SHALL NOT BE MOVABLE WITH A PRY BAR. ROCKS SHALL BE TIGHTLY NESTED (LOCKED TOGETHER) WITH ALTERNATING JOINTS AND WITH LARGER ROCKS AT BOTTOM. RIPRAP SHALL BE FREE DRAINING THROUGH SMALLER RIPRAP FILLED VOIDS. EACH ROCK SHOULD REST ON AT LEAST TWO ROCKS BELOW IT.

PART IV: OTHER INFORMATION

State Timber Sale Contract
No. 341-06-24
Mike Pine

WRITTEN PLAN

SALE NAME:

Mike Pine

PROTECTED WATERS:

A medium, fish, unnamed tributary of Michael Creek.
Unnamed tributary to North Fork Trask River.

LOCATION:

Portions of Sections 14, 15, 22, and 23 T1S, R7W, W.M.,
Tillamook County, Oregon.

Riparian Management Area:

The area measured 100 feet slope distance from the high water mark on the protected waters.

Protection Measures:

Yarding Systems, Layout, and Stream Protection

When yarding with cables hanging within or across the streams, cables will be pulled out of the Riparian Management Area prior to rigging the next yarding road. Yarding roads will be spaced an average of 150 feet apart where they extend over or through the riparian management area.

Date: July 11, 2005
By: Ed Wallmark